

ABSTRACT

**me of Work :-Construction of public toilet block 8 seats(Gents)& 8 seats (Ladies) at
ayate Wasti Road ,Peth Somwar, for PMC Phaltan.**


Unit	Quantity	Item No	Item	Rate	Amount
cum	107.81	1	Dismantling brick masonry in lime or cement mortar & stacking the material as directed with all leads & lifts comp.as directed by engineer incharge(46.09)	351.75	37921.83
cum	15.72	2	Removing richmix cement concrete including stacking the material as directed with all leads & lifts comp.as directed by engineer incharge(46.13)	976.50	15349.35
cum	46.94	3	Removing sludge & Cleaning of existing septic tank by suction pump vehicle.	735.00	34500.31
cum	105.98	4	Excavation for foundation in earth, soil of all types, sand, gravel & soft murum, in-cluding removing the excavated material up to a distance of 50m. beyond the bldg. area & stacking & spreading as directed, dewatering, preparing bed for the foundation & necessary back filling, ramming, watering including shoring and strutting etc. comp. (lift upto 1.5m)(21.02)Spec.No.:Bd A. 1 Page No. 259	250.95	26594.83
cum	34.78	5	Excavation for foundation in Hard Murum, incl. removing the excavated material up to a distance of 50m. beyond the building area & stacking & spreading as directed, dewater -- ing ,preparing the bed for foundation & necessary back filling, ramming, watering including shoring and strutting etc. comp.(lift upto 1.5m to 3.00 m) (21.08) Spec. No. : Bd A. 21 Page No. 259	434.70	15119.23
Cum	311.22	6	Conveyance of unwanted stuff excavated material for 2 KM	182.70	56860.70
cum	22.86	7	Providing dry/trap/granite/quartzite/gneiss rubble stone solling 15 to 20 cm thick including hand packing and compacting comp. spec. No. : Bd A. 12 Page No. 264 (21.38)	2053.80	46941.60
cum	29.46	8	Providing & laying in situ CC in M-10 of trap/ granite/ quartzite / gneiss metal for foundation & bedding incl. belling out water farm work compact ing , curring comp. with fully automatic micro processor based PLC with SCADA enabled reversible drum type mixer with fine aggregates (crushed sand VSI garde) spec. No. Bd E. 1 Page No. 287 (24.01)	6580.40	193867.60
cum	7.65	9	Providing and casting in situ cement concrete M-20 of trap / granite/quartzite gneiss metal for RCC beams & lintels as per detailed design drawing as directed including centering form work, cover blocks, compaction androughening the surface is special finish is to be provided and curring complete (excluding reinforcement) with fully automatic micro processor based PLC with SCADA enabled reversible drum type concrete mixer withfine aggregates(crushed sand VSI garde) Spec No. Bd F 6 Page no. 300 & B-7 Page No. 38 (25.41)	13285.90	101644.26

	25.32	10	Providing and casting in situ cement concrete M-20 of trap /granite/quartzite gneiss metal for RCC Slab as per detailed design drawing as directed including centering form work cover blocks, compaction and roughening the surface is special finish is to be provided and curring comp. (excluding reinforcement)with fully automatic micro processor based PLC with SCADA enabled reversible drum type concrete mixer with fine aggregates(crushed sand VSI garde)(25.61) Spec No. Bd F 9 Page no. 303 & B-7 Page No. 38	15043.60	380868.75
MT	3.220	11	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for RCC pile caps footings, foundations, slabs, beams, columns, canopies, stair case, newels and chajjas lintel, pardi, copings fins, arches etc.as per detail designs, drawings and schedule including cutting bending, hooking the bar binding with wire or tack welding and supporting as required complete Spec. No. Bd F 17 Page No. 306 (26.33)	94188.15	303285.84
cum	3.31	12	Providing uncoursed rubble masonry of trap metal in CM 1:6 in foundation & plinth of inner wall/external wall incl. bailing out water manually stacking joints on unexposed faces & watering etc.comp.BDH1 Page No.329(28.01)	6002.60	19855.76
Cum	29.77	13	Providing second class burnt brick masonry with conventional/IS type in CM1:6 in foundation and plinth of inner wall / in plinth external wall including bailing out water striking joints on unexposed faces racking out joint on exposed faces & watering comp.Spec. No. Bd G 1 Page No. 313 (27.01)	8274.15	246326.58
Cum	55.11	14	Providing second class brick masonry with conventional IS type in cement mortar 1:6 in Superstructure including bailing out water striking joints on unexposed faces racking out joint on exposed faces and watering complete. Spec. No. BDG 2 & 5 Page No. 313 (27.05)	8525.10	469845.52
sqm	53.77	15	Providing internal cement plaster 12 mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surface in all positions including,scaffolding & curring complete.Spec. No. Bd L 2 Page No. 368 (32.04)	298.05	16026.27
sqm\	572.47	16	Providing internal cement plaster 20 mm thick in two coats in cement mortar 1:5 without neeru finish to concrete or brick surface in all positions including,scaffolding & curring complete.Spec. No. Bd L 4 Page No. 368 (32.07)	411.35	235485.53
sqm	626.24	17	Providing neeru finish to plastered surface in all positions including, scaffolding & curring complete Spec No. Bd L 10 Page no. 370 (32.15)	68.25	42740.91
sqm	258.62	18	Providing sand faced plaster externally in cement mortar using aproved screened sand in call positions including base coat of 15 mm thick in cm 1:4using waterproofing compound at 1 Kg per cement bag curring the same for not less than two days and keeping the surface of the base coat rough to receive the sand faced treatment 6to8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curring for the 14 days scaffolding etc.comp. spec. No. Bd L. 7 Page no. 369 (32.11)	684.50	177026.90

	14.00	28	Providing & fixing Orissa type white glazed earthenware 575 mm water closet pan incl. S trap with earthenware foot rests, cast iron soil & vent pipe upto outside face of the wall 1:2:4 brick bat lime concrete bedding without flushing tank and its accessories etc. complete. Spec. No.: As directed by Engineer in charge. (42.33)	4207.35	58902.90
No.	2.00	29	Providing & fixing European type white glazed earthen ware water closet pan with UPVC seat & lid with chrom - -ium plated brass hinges & rubber buffer incl. UPVC & vent pipe upto the outside face of wall 10 litre enameled low level flushing cistern with fittings pipe stop tap bracket for a fixing cistern 32mm dia. UPVC flush pipe with fittings & clamps 20mm dia. UPVC over flow pipe mosquito proof coupling G.I. chain & pulley with water jet & fittings including cutting & making good to wall & floors testing etc. comp. (Prior approval of sample & brand by Ex. Engineer is necessary before use) BDV 21(43.19)	12175.80	24351.60
No.	30.00	30	Providing and fixing 15 mm dia. screw down bib/ stop tap of brass including necessary socket union nut comp. Spec. No.: Bd.V.8 Page No. 554(41.40)	704.55	21136.50
No.	4.00	31	Providing & fixing 25 mm dia. screw down bib/stop tap of brass including necessary socket union nut complete. Spec. No.: Bd.V.8 Page No. 554 (41.42)	1434.30	5737.20
No.	4.00	32	Providing & fixing white glazed earthenware wash hand Basin of 55cm.x40cm.size including cold water pillar tap/ cold & hot water pillar tap brackets rubber plugs & brass chain, stop tap and necessary pipe connections including P.V.C. waste pipe & trap up to the outside face of the wall .Spec. No.: Bd.V.30 Page No. 565 (41.63)	5878.95	23515.80
No.	4.00	33	Providing & fixing 8cm C.I. Nahani Trap including C.I. grating bend & piece of C.I. pipe upto the outside face of the wall complete.Spec. No.: Bd.V.32 Page No.567 (41.79)	851.55	3406.20
Ltr	2000.00	34	Providing & fixing H.D.P container Syntex or alike one piece moulded water tank made out of high density poly thylar & built corrugated inclusive of delivery up to destination hoisting & fixing of acces. such as inlet, outlet overflow pipe incl. of all taxes capacity between 200- to 1000 litSpec.No.:As directed by engineer-in-charge (42.54)	11.55	23100.00
Rmt	100.00	35	Providing & fixing on walls/ceiling/floor 15mm dia CPVC pipe with necessary fittings,remaking good the demolished portion etc.comp.Spec. No.: BD.V 5 page 551& as directed by Engineer in charge (42.55)	279.30	27930.00
Rmt	20.00	36	Providing and fixing on walls/ceiling/floor 25 mm dia. CPVC pipe with necessary fittings, remaking good the demolished portion etc. comp.Spec. No.: BD.V 5 page 551 & as directed byEngineer in charge (42.57)	393.75	7875.00
No.	2.00	37	Providing & fixing cromium plated towel rod 16mm dia & 75 cm in length including all accessories etc. comp (42.31)	313.95	627.90
No.	2.00	38	Providing & fixing 450mm X550mm superior type Belgium mirror with 16mm dia Nickel plated towel rod etc. comp.(42.20)	904.05	1808.10
Pts	30.00	39	Point wiring for indipendent plug in 20mm metal conduit with 1.5mm sqmm FRLSH grade copperwire switch earthing & required accessories as per specification no.(WG-PW/SW) (1-7-2)	941.00	28230.00

	2.00	40	Supply & erecting exhaust fan medium duty 230 watt AC 50 cycle 225mm 1400 RPM with condenser comp. erected in position with necessary material.Fan motar with moisture proof treatment & E class ensulation.(2-10-15)	2032.00	4064.00
os.	24.00	41	Supplying & erecting 10-12 watt,230V integral type LED Lamp sutable for B-22/E-27 base(2-8-11)	230.00	5520.00
sqm	626.24	42	Providing & applying washable oil-bound distemper of approved colour & shade to old & new surfaces in two coats including scaffolding,preparing the surfaces.(excl. the primer coat.)comp.Spec. No:Bd.P.5 Page No.413(36.11)	88.20	55234.40
sqm	258.62	43	Providing & applying two coats of waterproof cement paint of approved manufacture & of approved colour to the plastered surfaces including cleaning ,& preparing the plaster surface scaffolding if necessary , & watering the surfacefor two days completeBDO8 page.406(35.13)	82.95	21452.71
sqm	2.05	44	Providing sills of polish kadappa stone 25 to 30 mm thk. On bed of CM 1:4 including cement float filling joints curing,polishing,cleaning etc.comp.(33.20)	1138.20	2334.45
No	1.00	45	Providing & fixing 90x60 cm. granite plate engraving 10cm height letter figures painting with approved colour & shade comp.Spec No.Bd.W 7 page no.586 (44.12)	9058.35	9058.35
				Total	3362473.83
				Say	3362474.00


Jr.Engineer
PhaltanMuncipal Council


City Engineer
PhaltanMuncipal Council


Chief Officer
PhaltanMuncipal Council